



#### **FLOW – Jamie Holling**









- Long history of use in the marine Environment
- Shrinking Environmental impact (EPD)
- Durability over 50 years
- Locally sourced
- Recycled content
- Recyclability
- Traditional construction methods

#### **Blyth Offshore Wind Farm**





#### **Steel Making & Fabrication Sites UK**





- **O** Fabricator
- Mesh Producer



#### **Electric Arc Furnace Technology**







Reinforcing bars For the reinforcement of concrete (Grade 500C)



High Yield Coils For the reinforcement of concrete (Grade 500C)





- Currently B500C grade (Cardiff) 98 % recycled content 100%UK sourced
- Standard diameters and lengths

- Possible B550C or B600C grade
- Intermediate diameters: e.g. 22mm, 28mm, 36mm, 42mm
- Intermediate lengths: e.g. 11m, 13m, 17m

#### Quantity Driven

#### **Local Plants**



- Nearest existing plants Motherwell and Whitburn
  - Joint capacity 800t cut and bent bar per week

- Ardesier 180 miles
- Kishorn 240 miles
- Thurso 280 miles

No skills/rebar fabrication north of the M8



Minimum, x2 close to shore facilities required in northern Scotland

- Specialist automated machinery required (12-18 month lead time)
- Bespoke factory units to accommodate machinery (2-3 years)
- Approximately 100m x 50 m factory plus storage/yard
- Workforce: 70-100 per site

### **Logistical Options**



- Shipping direct to port facility
  - Cardiff to Ardesier 850 miles (3.5 days)
  - Cardiff to Thurso 750 miles (3 days)
  - Cardiff to Kishorn 600 miles (2.5 days)

- Minimum 5000t per shipment
- One every 10-12 days at peak demand

Possible rail link

#### **Manufacturing Options**



- Group rebar capacity
- New Steel mills in Scotland?

- UK fabrication
- Factories close to port facilities?

- Robotics/automation
- Key factors (12-18 months lead time)
- Bespoke factory to suit automation

#### **Technical Solutions**



Technical solutions for offshore bases

Rebar

- Coupler systems
- PT
- Formwork
- Concrete



# Questions WelcomeBRC Ltd Stand D26

## Jamie.holling@brc.ltd.uk